

Prasar Bharti
Broadcasting Corporation of India,
Office of the Assistant Engineer (E)
CCW:AIR, DDB Phase-II, Copernicus Marg, Mandi House
New Delhi - 110 001.

No. 14(2)/AE(E)/MH-II/2010-11/52

Date : 7-7-2010

Notice Invitation Quotation

Sealed quotation are invited on behalf of President of India on item rate for the item noted supply / work so as to reach to undersigned on or before 14-7-2010 by 3.00 p.m.

The quotation shall be opened on the same day at 3.30 p.m. The quotation should be subscribed Quotation for (*) due on 14-7-2010

(*)Name of Work : **Electrical Wiring i/c ITC of fittings in DDK store lower basement at DDK, Mandi House, New Delhi.**

S/N.	Description of Item	Qty.	Rate	Unit	Amount
------	---------------------	------	------	------	--------

--- As per schedule of work attached---

Terms & Conditions :

1. The Work shall be carried out as per CPWD specification.
2. The rates quoted by the agency should be net & inclusive of all taxes & cartage, octroi. No advance payment shall be made on this account.
3. Time allowed for completion of work is 10 days.
4. The dismantled material should be returned to JE(E) concerned if any.
5. The undersigned reserved the right to reject any or all the quotation without assigning any reason.

Issued to : _____

Assistant Engineer(E)

Copy to :

- 1) The Superintending Engineer, AIR, 6th floor, NBH, Sansad Marg, New Delhi with the request to upload this tender notice at All India Radio, tender website.
- 2) The Executive Engineer(E)-II, CCW:AIR, Pushpa Bhawan, New Delhi.
- 3) Notice Board

AE-Continer


7/7

Assistant Engineer(E)
CCW, AIR, Doordarshan Bhawan
Mandi House, Phase-II, New Delhi-1
42/07/10

Schedule of Work

Name of work : Electrical Wiring i/c ITC of fittings in DDK store lower basement at DDK, Mandi House, New Delhi.

S/N	Description of work	Qty.	Unit	Rate	Amount
1	Wiring for light point / fan point / exhaust fan point / call bell point with 1.5 sqmm FR PVC insulated copper conductor single core cable in surface / recessed PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sqmm FR PVC insulated copper conductor single core cable etc. complete as required - Group "C"	20 Points	Pts.		
2	Wiring for circuit / submain wiring alongwith earth wire with the following sizes of FR PVC insulated copper conductor, single core cable in surface/recessed steel conduit as required.				
a	2 x 2.5 Sqmm + 1 x 2.5 sqmm earth wire	55 Mtrs.	M		
3	Installation, testing and commissioning of pre-wired fluorescent fittings/ compact fluorescent fitting of all types, complete with all accessories and tube etc. directly on ceiling / wall, i/c connection with 1.5 sqmm FR PVC insulated, copper conductor, single core cable and earthing etc. as reqd.	20 Nos.	Each		
Grand Total					


Assistant Engineer(E)
Asstt. Engineer (E)
CCW, AIR, Doordarshan Bhawan
House, Phase-II, New Delhi-1